



ESTIMATED EARTHWORK QUANTITIES (cy)

ITEM	CUT	FILL	TOPSOIL	EXCESS
PAD	18259	11357	6000	902
PIT	0			0
TOTALS	18259	11357	6000	902

REVISED: 7/16/13

136 East Third Street
Rifle, Colorado 81650
Ph. (970) 625-2720
Fax (970) 625-2773



BOOKCLIFF
Survey Services, Inc.

SCALE: 1" = 100'
DATE: 6/14/13
PLAT: 2 of 7
PROJECT: Kokopelli
DFT: cws

*NOTES:

- 1.) Topsoil Volume Based on 12" Soil Depth.
- 2.) 10% Swell Factor Applied to Earthwork Cut Volume.
- 3.) Total Disturbed Area = ±6.45 ac.

Construction Plan Prepared for:
WPXENERGY WPX Energy Rocky Mountain, LLC

KP 32-9 Drill Pad - Plat 2
CONSTRUCTION LAYOUT