

Smith Energy Corp

API# 05-121-10870

Longknife 23-28

NESW Section 28 T2S-R50W, 6th pm
(1775'FSL, 1660'FWL)

Best Management Practices Summary

Stormwater Management Plans (SWMP) will be in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE). BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. The BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.

Spill Prevention Control and Counter measures (SPCC) plans will be in place to address any possible spills associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR12.

Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup will be required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup will consist of patrolling the roadways, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.

The above BMP's will be provided to all HRM's employees, contractors and will be posted in the company trailer located on location during drilling, completion and production operations.