

### Geologist Information

General: Existing location, 2 new Nio wells (4 existing WF wells)  
Ownership: WPX Surface, Fee Minerals  
SUA Status: Needed for pipelines?  
Spacing Units: 2-section spacing  
Adjacent Owners: Exxon Mobil Oil Corp

6S 96W

WPX ENERGY  
ROCKY  
MOUNTAIN, LLC

MOBIL  
OIL CORP

### Plan of Development

**Access** Use existing access. Will need to raise road to get onto pad due to pad fill.

**Drilling:** Nabors X21 Rig

**Cuttings:** To be managed on surface along north edge of pad.

**SIMOPS:** No

**Completions:** Frac on pad after rig leaves. Water supplied via 2-4.5" temporary surface steel supply lines, tying into proposed Wheeler Gulch frac water supply infrastructure.

**Flowback:** On pad.

**Production:** Shift tank and separator areas south to stay off pad fill. 50'x30' for separators, 55'x55' for tanks.

**Pipeline:** Upgrade to 8" gas line and add 4" water line and tie into existing infrastructure along Wheeler Gulch road. Will need and additional 10' of ROW.

### Legend

- Proposed Cuttings Management Area
- Proposed Production Equipment Area
- Proposed Daylight Line
- Proposed Pad or Pit
- Existing Production Equipment
- Proposed Frac Water Supply Line (Temp, Surface, Steel)
- Williams Gas Line
- Parcel Ownership (from Garfield County)



0 100 200 400 Feet

WPX Energy Rocky Mountain, LLC

GM 14-27 Plan of Development  
T6S R96W, Section 27

November 19, 2014

