

**FORM
INSP**

Rev
X/20

**State of Colorado
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:

09/15/2023

Submitted Date:

09/18/2023

Document Number:

708901693

FIELD INSPECTION FORM

Loc ID: 322298 Inspector Name: Smelser, Wayne On-Site Inspection: 2A Doc Num: _____

Status Summary:

THIS IS A FOLLOW UP INSPECTION

FOLLOW UP INSPECTION REQUIRED

NO FOLLOW UP INSPECTION REQUIRED

Findings:

14 Number of Comments

3 Number of Corrective Actions

Corrective Action Response Requested

Operator Information:

OGCC Operator Number: 10550

Name of Operator: MUSTANG RESOURCES LLC

Address: 1660 LINCOLN STREET SUITE 1450

City: DENVER State: CO Zip: 80264

ANY CORRECTIVE ACTION(S) FROM PREVIOUS INSPECTIONS THAT HAVE NOT BEEN ADDRESSED ARE STILL APPLICABLE

Contact Information:

Contact Name	Phone	Email	Comment
Mustang		nwelch@vaqueroenergy.com	
Toews, Wesley		wtoews@blm.gov	

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
210183	WELL	PR	12/01/2017	GW	045-05078	JUHAN FEDERAL 1-35-6S-94W	PR

General Comment:

[CECMC Inspection Report Summary](#)
 On 09/15/2023 at approximately 08:41 hours, I, Compliance Specialist, Wayne Smelser Conducted an on-site inspection at MUSTANG RESOURCES LLC JUHAN FEDERAL 1-35-6S-94W Pad. Location # 322298 in Garfield County Colorado. Location is within High Priority/Density/Black Bear Habitat areas & in close proximity to NSO Habitat area. Location is approximately 217 yards from Porcupine Creek. While there, I observed normal production operations.

During this inspection the following compliance issues were observed:

1. Signs/Marker - Tank not properly labeled, missing required information with a CA date of 10/18/2023
2. Equipment - PRV vent & rupture disc vent lack caps with a CA date of 09/25/2023
3. Tanks & Berms - Secondary containment not sufficient to contain spilled or released materials with a CA date of 10/18/2023

A follow up on this site inspection needs to be conducted to ensure the compliance issues have been corrected to comply with CECMC rules.
 This is a summary of inspection report.

Location

Lease Road:			
Type	Access		
comment:			
Corrective Action			Date:

Overall Good:

Signs/Marker:			
Type	BATTERY		
Comment:			
Corrective Action:			Date:
Type	TANK LABELS/PLACARDS		
Comment:	Tank not properly labeled, missing required information.		
Corrective Action:	All Tanks with a capacity of 10 Barrels or greater will be labeled or posted with the following information: A. Name of Operator; B. Operator's emergency contact telephone number; C. Tank capacity; D. Tank contents; and E. NFPA label or equivalent globally harmonized label.		Date: 10/18/2023
Type	OTHER		
Comment:	Separator unit includes attached storage tank. The sight glass located on the side of the unit indicates the storage tank is full of an unknown fluid. No form of labeling or markers are present to identify a potential hazard or the contents of the storage tank.		
Corrective Action:			Date:
Type	WELLHEAD		
Comment:			
Corrective Action:			Date:

Emergency Contact Number:			
Comment:	911/888-291-8588		
Corrective Action:			Date: _____

Overall Good:

Spills:			
Type	Area	Volume	

In Containment: No _____

Comment: _____

Multiple Spills and Releases?

Equipment:			corrective date
Type: Other	# 2		
Comment:	PRV vent & rupture disc vent lack caps		
Corrective Action:	Vents on pressure safety devices will terminate in a manner so as not to endanger the public or adjoining facilities. They will be designed to be clear and free of debris and water at all times.		Date: 09/25/2023
Type: Gas Meter Run	# 1		
Comment:			

Corrective Action:		Date:	
Type: Bradenhead	# 1		
Comment:	No form of pressure monitoring equipment located on bradenhead, bradenhead valve is accessible.		
Corrective Action:		Date:	
Type: Horizontal Heated Separator	# 1		
Comment:			
Corrective Action:		Date:	
Type: Deadman # & Marked	# 5		
Comment:	Marked		
Corrective Action:		Date:	
Type: Bird Protectors	# 1		
Comment:			
Corrective Action:		Date:	
Type: Plunger Lift	# 1		
Comment:	Well on plunger lift		
Corrective Action:		Date:	

Tanks and Berms:

Contents	#	Capacity	Type	Tank ID	SE GPS
PRODUCED WATER	1	400 BBLs	STEEL AST		
Comment:					
Corrective Action:					Date:

Paint

Condition	Adequate
Other (Content)	
Other (Capacity)	
Other (Type)	

Berms


Type	Capacity	Permeability (Wall)	Permeability (Base)	Maintenance
Earth	Inadequate			Inadequate
Comment:	Secondary containment not sufficient to contain spilled or released materials/containment capacity not 110% of 400 bbl tank.			
Corrective Action:	Repair or install berms or other secondary containment devices.			Date: 10/18/2023

Venting:

Yes/No	NO
Comment:	
Corrective Action:	Date:

Flaring:

Type	
Comment:	
Corrective Action:	Date:



Inspected Facilities

Facility ID: 210183 Type: WELL API Number: 045-05078 Status: PR Insp. Status: PR

Producing Well

Comment: [Producing, well on plunger lift](#)

Corrective Action:

Date:

Reclamation - Storm Water - Pit

Storm Water:

Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment
		Gravel				
Compaction						Light compaction
Gravel						Sparse
		Compaction				

Comment: Location appears to have some gravel throughout the location with light compaction. Places with sparse to no gravel are present on location. Sparse gravel and light compaction could lead to future stabilization and tracking issues.

Corrective Action:

Date: _____

Pits: NO SURFACE INDICATION OF PIT

COGCC Comments

Comment	User	Date
Please refer to Signs/Marker, Equipment & Tanks & Berms for observed compliance issues.	smelserw	09/18/2023

Attached Documents

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
403533862	INSPECTION SUBMITTED	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6254923
708901694	Inspection 708901693 Stormwater photo log	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6254921
708901695	Inspection 708901693 photo log	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=6254922